



University of the Philippines Visayas  
Tacloban College  
**BIDS AND AWARDS COMMITTEE**



**BID BULLETIN NO. 4**  
03 August 2022

**Project: FLOOR SLAB RETROFITTING OF THE UPV TACLOBAN COLLEGE LIBRARY BUILDING  
(PORTION OF SECOND & THIRD FLOORS ONLY)**

This Bid Bulletin is hereby issued to clarify the query of Melil Construction and Supply sent through email on 03 August 2022.

Query	Response
<p>Please provide details of the following:</p> <ol style="list-style-type: none"><li>1. Size of Base Plate</li><li>2. Size of Existing Concrete Column</li><li>3. Size of Web Brace</li></ol> <p><i>Referring to Drawings Sheet No. S9-9/9</i></p>	<ol style="list-style-type: none"><li>1. As to thickness, it is 12mm thk. base plate as labeled in the plan. As to dimension, it will depend on the actual position or the size of the I-beam.</li><li>2. Average size of column ranges from 0.50m x 0.50m to 0.60m x 0.60m Refer to actual site.</li><li>3. Size of the web brace is 12mm and it is also labeled in the plan. It will also depend on the actual position and size of the I-beam. Refer to Sheet Nos. S7-9/7 and S9-9/9</li></ol>

For the guidance and information of all concerned.

  
**ARVIN L. DE VEYRA**  
BAC Chairperson